

WELCOME TO KCP SOLAR POWER PLANT

Mr. K.C.SRINIVASA RAO
GENERAL MANAGER (E&I)
9491296011, kcsao@kcp.co.in

THE KCP LIMITED
KCP CEMENT – UNIT-II
RAMAKRISHNAPURAM-521457

KCP Group of Companies CEMENT DIVISION



CEMENT UNIT-I- 0.80 MTPA



CEMENT UNIT-II – 1.52 MTPA

KCP Group of Companies

RENEWABLE ENERGY DIVISION(14.95 MW)



8.25 MW



3.25 MW



1.15 MW



2.30 MW WHR



Green power zone

KCP SOLAR
VISION IN ACTION

Capacity : 1.15 MWp DC with single Axis Tracker

CAPTIVE SOLAR PHOTOVOLTIC POWER PLANT
THE KCP LIMITED, RAMAKRISHNAPURAM

PROJECT DETAILS

Location: Muktyala, Jaggayyapet(m),
Krishna(D), AP

- ❖ Capacity: 1.15 MWp
- ❖ Scheme: REC Mechanism
 - Embedded connection with cement plant
- ❖ Single axis tracker
- ❖ Poly Crystalline SPV 240 Wp
- ❖ Land Occupied: 5.50 Acres
- ❖ Module Area : 8217 m²

PROJECT DETAILS

- ❖ Energy guaranteed: 19,08,000 kwh/yr
- ❖ First 2 years O&M Inclusive
- ❖ SPV Panels 25 years warranty
- ❖ BOS 5 years warranty
- ❖ Solar Fencing Inclusive
- ❖ Solar LED Street lights
- ❖ CCTV : IR PTZ Camera
- ❖ Lightening Arrestors – 3 no

•Year wise Generation Guarantee for 25 Years

<u>Year #</u>	<u>Annual Energy Output guarantee(KWh)</u>	<u>Max. YoY Degradation</u>
1	1908016	0
2	1892752	0.8%
3	1877610	0.8%
4	1862589	0.8%
5	1847688	0.8%
6	1832907	0.8%
7	1818244	0.8%
8	1803698	0.8%
9	1789268	0.8%
10	1774954	0.8%
11	1760754	0.8%
12	1746668	0.8%
13	1732695	0.8%
14	1718833	0.8%
15	1705083	0.8%
16	1691442	0.8%
17	1677910	0.8%
18	1664487	0.8%
19	1651171	0.8%
20	1637962	0.8%
21	1624858	0.8%
22	1611859	0.8%
23	1598964	0.8%
24	1586173	0.8%
25	1573483	0.8%

TECHNICAL EVALUATION

Grid-Connected System: Simulation parameters

Project : Jaggayyapet

Geographical Site Jaggayyapet **Country** India

Situation Latitude 16.1°N Longitude 80.0°E
 Time defined as Legal Time Time zone UT+6 Altitude 107 m
 Monthly albedo values

	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sep.	Oct.	Nov.	Dec.
Albedo	0.16	0.16	0.16	0.16	0.15	0.16	0.16	0.17	0.16	0.16	0.16	0.16

Meteo data : Jaggayyapet_New, Synthetic Hourly data

Simulation variant : KCP_1.15MW_Tracker_Bonfiglioli RPS 1110

Simulation date 18/09/12 13h44

Simulation parameters

Tracking plane, tilted Axis Axis Tilt 0° Axis Azimuth 0°
 Rotation Limitations Minimum Phi -45° Maximum Phi 45°

Backtracking strategy Tracker Spacing 4.80 m Collector width 1.66 m
 Inactive band Left 0.02 m Right 0.02 m

Horizon Free Horizon

Near Shadings No Shadings

PV Array Characteristics

PV module Si-poly Model **SSI-M6-230**
 Manufacturer Solar Semiconductor
 Number of PV modules In series 25 modules In parallel 200 strings
 Total number of PV modules Nb. modules 5000 Unit Nom. Power 230 Wp
 Array global power Nominal (STC) **1150 kWp** At operating cond. 1026 kWp (50°C)
 Array operating characteristics (50°C) U mpp 653 V I mpp 1572 A
 Total area Module area **8217 m²** Cell area 7302 m²

Inverter Model **RPS 1110 Multi MPPT**
 Manufacturer Bonfiglioli Vectron
 Characteristics Operating Voltage 460-875 V Unit Nom. Power 1000 kW AC

PV Array loss factors

Thermal Loss factor U_c (const) 25.7 W/m²K U_v (wind) 0.0 W/m²K / m/s
 -> Nominal Oper. Coll. Temp. (G=800 W/m², Tamb=20°C, Wind=1 m/s.) NOCT 47 °C
Wiring Ohmic Loss Global array res. 13 mOhm Loss Fraction 2.8 % at STC
Array Soiling Losses Loss Fraction 3.0 %
Module Quality Loss Loss Fraction 1.5 %
Module Mismatch Losses Loss Fraction 2.0 % at MPP
Incidence effect, ASHRAE parametrization IAM = 1 - bo (1/cos i - 1) bo Parameter 0.05

TECHNICAL EVALUATION

PVSYST V5.57

18/09/12 Page 3/4


Grid-Connected System: Main results

Project : Jaggayyapet
Simulation variant : KCP_1.15MW_Tracker_Bonfiglioli RPS 1110


Main system parameters	System type Grid-Connected	
PV Field Orientation	tracking, tilted axis, Axis Tilt	0°
PV modules	Model	SSH-M6-230
PV Array	Nb. of modules	5000
Inverter	Model	RPS 1110 Multi MPPT
User's needs	Unlimited load (grid)	
	Axis Azimuth	0°
	Pnom	230 Wp
	Pnom total	1150 kWp
	Pnom	1000 kW ac

Main simulation results
 System Production **Produced Energy** 2002 MWh/year **Specific prod.** 1741 kWh/kWp/year
 Performance Ratio PR 77.5 %

Normalized productions (per installed kWp): Nominal power 1150 kWp



Performance Ratio PR



KCP_1.15MW_Tracker_Bonfiglioli RPS 1110

Balances and main results

	GlobHor [kWh/m²]	T Amb [°C]	GlobInc [kWh/m²]	GlobER [kWh/m²]	EArray [MWh]	E_Grid [MWh]	ERA/rR [%]	ERSysR [%]
January	140.7	21.20	186.1	184.0	175.7	169.0	11.37	10.99
February	155.1	22.60	201.7	198.0	185.7	173.5	11.20	10.83
March	194.7	24.60	251.5	247.6	235.7	220.9	11.07	10.69
April	195.9	25.50	246.5	243.0	223.5	215.0	11.03	10.66
May	187.5	27.30	229.5	225.7	207.1	200.0	10.99	10.62
June	144.0	27.50	166.1	162.5	152.5	147.6	11.18	10.82
July	129.3	26.60	145.5	142.1	134.4	130.0	11.24	10.87
August	132.1	26.50	150.1	146.0	139.2	134.6	11.28	10.91
September	135.9	25.70	158.0	154.8	145.6	140.0	11.21	10.84
October	134.5	24.00	181.0	157.7	150.8	146.0	11.40	11.03
November	135.9	22.40	170.2	166.5	159.4	154.2	11.39	11.02
December	130.6	21.10	179.6	175.3	165.3	162.0	11.40	11.03
Year	1629.3	24.50	2247.5	2203.0	2071.0	2002.1	11.21	10.84

Legende: GlobHor Horizontal global irradiation EArray Effective energy at the output of the array
 T Amb Ambient Temperature E_Grid Energy injected into grid
 GlobInc Global incident in cell plane ERA/rR Effic. Eout array / rough area
 GlobER Effective Global, corr. for IAM and shading ERSysR Effic. Eout system / rough area


TECHNICAL EVALUATION

Grid-Connected System: Loss diagram


Project : Jaggayyapet
Simulation variant : KCP_1.15MW_Tracker_Bonfiglioli RPS 1110

Main system parameters	System type	Grid-Connected		
PV Field Orientation	tracking, tilted axis, Axis Tilt	0°	Axis Azimuth	0°
PV modules	Model	SSI-M6-230	Pnom	230 Wp
PV Array	Nb. of modules	5000	Pnom total	1150 kWp
Inverter	Model	RPS 1110 Multi MPPT	Pnom	1000 kW ac
User's needs	Unlimited load (grid)			

Loss diagram over the whole year



KCP SOLAR PLANT 1.15 MWp LAYOUT




NOTES :

- T-01 - 24 Strings
- T-02 - 24 Strings
- T-03 - 22 Strings
- T-04 - 22 Strings
- T-05 - 22 Strings
- T-06 - 22 Strings
- T-07 - 24 Strings
- T-08 - 24 Strings
- Modules/String = 24
- Total No of Strings = 206
- Total No of Modules = 4944

REV. NO.	DATE	BY	REASON/REVISION	APPROVED BY	DATE
01	01/01/2023	---	---	---	---
02	01/01/2023	---	---	---	---
03	01/01/2023	---	---	---	---


REVISED BY	APPROVED BY	DATE	REASON/REVISION	DATE
---	---	---	---	---
---	---	---	---	---

TRACKER / STRING LAYOUT




NOTE:

- +ve Cu EBXL-XLPO 4Sqmm Cable
- -ve Cu EBXL-XLPO 4Sqmm Cable
- 230Wp Modules
- 235Wp Modules
- 240Wp Modules




REV. NO.	DATE.	DCR#	PAGE AFFECTED	REASON FOR CHANGE	PREPARED BY
01	30.11.12	29	01	SCB Location has been changed	Jayach

DC SCHEMATIC



132KV Incomer from Sitapuram SS



Total Plant - Power Over view



GRID

-7492 kW



Cement Plant Load

7.85 MW



-170 kW

CPP



754 kW

SOLAR

PROJECT COMPLETION







09/05/2013 10:26





09/05/2013 10:33

SOLAR PLANT CONTROL ROOM



09/05/2013 10:27



**Solar Inverter 5 x 200 KWp - MPP
Input: 700 VDC & Output 360 VAC**



09/05/2013 10:23

6.6 KV HT VCB, ABB Unigear ZS



09/05/2013 10:24

STATUTORY ABT METERING SYSTEM

6.6KV / 360 V TRANSFORMER



Aux Transformer



UPS AND BATTERY CHARGER



DATA LOGGER (HMI)

SOLAR LIGHT

09/05/2013 10:26



SOLAR POWER FENCE



SOLAR MONITOR & SYSTEM
Pvt. Ltd.



CONTACT:
22, Old Solar, Jang Business
Complex, Pochampally, G.P.
Kalyandurg, MYSURU - 57
PH: 080 4310203, 01 98871 3333

SOLAR FENCE

09/05/2013 10:22

SOLAR STREET LIGHT



09/05/2013 10:22




12/05/2013 18:13



12/05/2013 17:59



**Single Axis Tracker based on
NASA data for given longitude and latitude**



PERFORMANCE DATA

Year	Guaranteed Yield (kwh)	Actual Yield (kwh)
2013	1908	1917
2014	1893	1901
2015	1063 up to Jun	1017 up to Jun



overview daily

12.07.15




Production



yield	kWp	24h	Values	Solar	Mod-T	Env-T	Wind

ALL	A1	A2	A3	A4	A5



current			day		
feeding power Pac	726900	W	yield	7117,68	kWh
generator power Pdc	734380	W		3327,51	€
inverter efficiency η	>98	%	specific yield	6,17	kWh/kWp
status	5xMPP, DATA		maximum value	870160	W
error	---		set value	4291,84	kWh
			actual	165,8	%

avoided CO₂-emission total: 3353,04 to

overview monthly


July
2015



Values



ALL	A1	A2	A3	A4	A5	+
						-



current

feeding power P_{ac}	794060	W
generator power P_{dc}	802830	W
inverter efficiency η	>98	%
status	5xMPP, DATA	
error	----	

month

yield	78234,83	kWh
	36574,78	€
specific yield	67,83	kWh/kWp
maximum value	7761,1	kWh
set value (cumulative)	55793,90	kWh
actual	140,2	%


overview yearly

2015



Values
✓

ALL	A1	A2	A3	A4	A5	+
✓						-



current		
feeding power Pac	787500	W
generator power Pdc	796310	W
inverter efficiency η	>98	%
status	5xMPP, DATA	
error	----	

year		
yield	1095081,48	kWh
	511950,59	€
specific yield	949,50	kWh/kWp
maximum value	190787,0	kWh
set value (cumulative)	1063149,72	kWh
actual (forecast : 1675 kWh/kWp)	103,0	%

SOLAR PROJECT TECHNO-ECONOMICS


Annual Generation	19.08 LKwh/Year
Unit Rate	Rs 8.65 Rs/Kwh (Rs. 5.15 – Supply to Cement plant. Rs. 3.50 from REC - till Mar 2017)
Sale Value of Energy	Rs. 164 Lacs/Year
Less Annual O&M	Rs. - 6.00 Lacs/ Year
Capital Investment	Rs. 800 Lacs
Simple pay back period	5 years
Life of the SPV Module	25 years

APPROVALS


KCP SOLAR POWER- 1.15 MWp

- ❖ Connectivity Approval
- ❖ Metering Scheme approval
- ❖ CEIG Approval
- ❖ Grid Synchronization Approval
- ❖ REC Accreditation
- ❖ REC Registration
- ❖ Plan approval from Fact. Dept
- ❖ **MoEF Approval not required**

Eligibility Criteria



Renewable Energy Certificate



- Sale of Renewable Energy under REC Scheme
 - Consume Electricity with in our cement Plant
 - Sale REC Component to Obligated entities through IEX / PXIL

REC Buyers

- Obligated Entities (RPO)
 - Distribution Companies
 - Open Access Consumers
 - Captive Power Consumers
- Voluntary Entities
 - Corporates under CSR
 - Individuals

REC Revised Price as per CERC

The Commission decided to retain the proposed amendment in the final Order. The following forbearance price and floor price are prescribed for dealing in Solar Certificates under the REC Regulations:

	Solar REC (INR/ MWh)
Forbearance Price	5800
Floor Price	3500

The above stated forbearance and floor prices shall remain valid for the control period upto financial year 2016-17 from the date of notification of this Order.

As per CERC Amendment -3

Practical Challenges faced during Execution - The KCP Limited

- Approvals took 6 months after project ready
- Proper guidelines were not in place at state agencies.
- Lack of clarity on roles & responsibility of various wings in E.B. for solar projects.
- Absence of metering protocols for in-house captive solar projects.

REC ACCREDITATION

CERTIFICATE OF ACCREDITATION

This is to certify that **THE KCP LIMITED** having/proposing to install its RE Generating station at "**KCP LTD Mukhtayal Village Jaggayapet Krishna dt A.P** " with capacity **5.75MW**, utilising **Solar PV (Solar)** has been granted Accreditation for its said RE Generating Station with effect from **08-04-2013**

This Accreditation is granted subject to fulfilling the Rules, Regulations and Procedures specified by the State Agency from time to time.

The validity of this certificate is mandated through ongoing surveillance.

Issue Date	Expiration Date	Certificate Number
08-04-2013	07-04-2018	AP0SLKCPLS001A080413

Date : 08-04-2013

Place : Andhra Pradesh


Authorised Signatory of the
Accreditation Agency

Chief Engineer/SLDC
Andhra Pradesh State Load Dispatch
APTRANSCO, Vidyut Soudha,
Centre
HYDERABAD - 500 082.
Room No. 611, 6th Floor, Vidyut
Soudha APTRANSCO, khairtabad

REC REGISTRATION



This is to certify that **THE KCP LIMITED** having/proposing to install its RE Generating station at "**KCP LTD Muktayal Village Jaggayapet Krishna dt A.P " Andhra Pradesh** with installed capacity **5.75 MW**, availing **5.75 MW** under REC Mechanisim, utilising **Solar PV (Solar)** has been registered with Central Agency as 'Eligible Entity' for its said RE Generating Station with effect from **10-05-2013**

This Registration is granted subject to fulfilling the Rules, Regulations and Procedures specified by the Central Agency from time to time.

The validity of this certificate is mandated through ongoing surveillance.

Issue Date	Expiration Date	Certificate Number
10-05-2013	09-05-2018	AP0SLKCPLS001R100513

Date : 10-05-2013

Authorised Signatory of the Central
Agency

Place : New Delhi

National Load Despatch Centre
National Load Despatch Centre, B - 9
Qutab Institutional Area, Katwaria Sarai
New Delhi - 110016

SOLAR WATER PUMP



SOLAR STREET LIGHT



BEFORE



AFTER



SOLAR WATER HEATER



TOTAL TOWNSHIP EQUIPPED WITH SOLAR WATER HEATERS

ROOFTOP SOLAR SYSTEM, CORPORATE OFFICE, CHENNAI, TN



Let us contribute towards a Clean and Green Power



Mr. K.C.S. RAO

9491296011, kcsrao@kcp.co.in

THANK YOU